

Activity sequence rules — v2 DRAFT

LeveLog / Blueview · Cast-in-place concrete and cold-formed steel · For review and sign-off by Roy Foster

Purpose. These rules drive which activity chips the app offers a Competent Person when filling the Daily Jobsite Log. The app reads yesterday's logged activity for a floor and offers the activities that can logically follow. This is a deterministic lookup, not a prediction — every suggestion traces to a prior signed log entry.

Changes in v2 (all from operator review of v1). Added the cold-formed steel superstructure loop as a separate branch. Added drainage board and filter fabric between waterproofing and backfill. Added underground plumbing before vapour barrier and cellar slab rebar. Added crane and hoist jumps to the superstructure cycle. Added temporary roof and weatherproofing between top-floor slab and finished roofing. Corrected the fit-out order so framing precedes or runs concurrent with MEP rough-in. Added firestopping between MEP rough-in and insulation.

Behaviour rules that apply to every table.

1. Suggestions rank the chip order. They never pre-select an answer.
2. "Other" is always visible as the last chip, never buried.
3. An activity entered under "Other" is remembered for that project and appears as a chip the next day.
4. Multiple activities may be logged for one floor on one day.
5. The CP may log any activity at any time. These rules order the list; they never block an entry.
6. Where two activities run concurrently in practice, both stay offered — the rule does not force one to finish first.

Branch selection. Section 3 splits by structural system. The app must know which system a project uses before it can offer the correct superstructure loop. This is set at project setup by the admin, or read from the structural drawings and confirmed by the admin before it becomes project state. If the system is unknown, the app offers both loops and states that the structural system has not been set.

1. Cold start — no prior day logged

Applies on the first logged day of a project, or when a floor has no prior entry. The app assumes the earliest phase and lets the CP correct it.

Condition	App offers next
Project start (no history)	Excavation, shoring, underpinning, piles, site prep
Existing project, state set manually	Whatever the CP selects once at setup, then rules run forward

2. Foundation phase

After this activity	App offers next
Excavation	Shoring, piles, footings, waterproofing, continue excavation
Shoring / underpinning	Excavation, piles, footings
Piles	Pile caps, footings, pile cut-off
Footings / pile caps	Foundation walls, grade beams, columns rebar
Foundation walls	Waterproofing, grade beams
Waterproofing	Drainage board / filter fabric , protection board

After this activity	App offers next
Drainage board / filter fabric	Backfill, protection board
Backfill	Underground plumbing , under-slab MEP, compaction
Underground plumbing	Under-slab MEP, vapour barrier, inspection
Under-slab MEP	Vapour barrier, cellar slab rebar
Vapour barrier	Cellar slab rebar
Cellar slab rebar	Pour cellar slab
Cellar slab	1st floor superstructure — see section 3

3. Superstructure cycle — repeats per floor

Two branches. Use 3A or 3B depending on the project's structural system. Floor N is the floor under construction; the transition activity opens floor N+1.

3A. Cast-in-place concrete

After this activity	App offers next
Columns / shear wall rebar	Columns / shear wall formwork
Columns / shear wall formwork	Pour columns / shear walls
Pour columns / shear walls	Strip column formwork, slab shoring and formwork
Slab shoring and formwork	Slab rebar, edge forms
Slab rebar	MEP sleeves and embeds, post-tension tendons, inspection
MEP sleeves and embeds	Pour slab
Pour slab (floor N)	Curing, strip formwork, reshore, floor N+1 columns / shear wall rebar
Curing	Strip formwork, reshore
Strip formwork	Reshore, patching, floor N+1 activities
Reshore	Floor N+1 activities, masonry, MEP rough-in on floor N

3B. Cold-formed steel (CFS)

After this activity	App offers next
Load-bearing CFS wall panels / studs (floor N)	Floor joists / corrugated metal decking, bracing
Floor joists / corrugated metal decking	Subfloor / structural sheathing
Subfloor / structural sheathing	MEP floor penetrations / sleeves
MEP floor penetrations / sleeves	Pour concrete topping slab, or CFS wall panels floor N+1
Pour concrete topping slab	Curing, floor N+1 CFS wall panels / studs
Curing (topping slab)	Floor N+1 CFS wall panels / studs

3C. Applies to both branches

After this activity	App offers next
Any floor structure complete	Crane jump, hoist jump , material hoisting
Crane jump / hoist jump	Resume floor N+1 superstructure activities

4. Topping out and envelope

After this activity	App offers next
Top floor slab / top floor structure complete	Temporary roof / weatherproofing , parapets, bulkhead, elevator overrun
Temporary roof / weatherproofing	Finished roofing, parapets, roof MEP
Finished roofing	Parapets, flashing, roof MEP
Any floor stripped and reshored / CFS floor complete	Masonry, façade, window install, framing
Masonry / façade	Window install, waterproofing, flashing
Window install	Façade close-out, interior framing

5. Interior fit-out

Order corrected in v2: framing precedes or runs concurrent with MEP rough-in, since rough-ins are secured to framing. Firestopping added between MEP rough-in and insulation.

After this activity	App offers next
Building envelope closed	Framing — layout, track and studs , insulation prep
Framing — layout, track and studs	MEP rough-in (concurrent), blocking, inspection
MEP rough-in	Firestopping , inspection, continue framing
Firestopping	Inspection, insulation
Insulation	Drywall, inspection
Drywall	Taping, finishes, flooring, paint
Taping	Paint, flooring, millwork
Finishes / flooring / paint	Fixtures, punch list, final inspection

6. Activities available on any day, regardless of phase

These are never sequence-gated. They appear as chips at all times.

Site clean-up · material delivery · hoisting · scaffold erection · scaffold dismantle · sidewalk shed work · dewatering · survey / layout · inspection · safety meeting · rain — no work · shutdown · **Other**

Sign-off

These rules govern activity suggestions inside a signed legal record. They must not ship unreviewed.

Reviewed by	
Title	

Signature	
Date	
Version approved	v2

Status: DRAFT — not approved. Sequence order reflects common practice plus operator review, and is not a substitute for the project's structural drawings, approved means and methods, or the site safety plan.